



DIMENSIONI STANDARD - STANDARD DIMENSIONS

LUCE DI PASSAGGIO DOORWAY		MISURE DI INGOMBRO OVERALL DIMENSIONS		PANNELLO PORTA (LEGNO) DOOR PANEL (WOOD)	
L x H	Z x HT	P	LT	LP	HP
600 x 2000/2030/2100	1330 x 2100/2140/2200	655	635	615 ÷ 630	2010/2040/2110
700 x 2000/2030/2100	1530 x 2100/2140/2200	755	735	715 ÷ 730	2010/2040/2110
800 x 2000/2030/2100	1730 x 2100/2140/2200	855	835	815 ÷ 830	2010/2040/2110
900 x 2000/2030/2100	1930 x 2100/2140/2200	955	935	915 ÷ 930	2010/2040/2110
1000 x 2000/2030/2100	2130 x 2100/2140/2200	1055	1035	1015 ÷ 1030	2010/2040/2110
1100 x 2000/2030/2100	2330 x 2100/2140/2200	1155	1135	1115 ÷ 1130	2010/2040/2110
1200 x 2000/2030/2100	2530 x 2100/2140/2200	1255	1235	1215 ÷ 1230	2010/2040/2110

PARETE FINITA - FINISHED WALL			
	150	174	200
H	500 ÷ 3000	500 ÷ 3000	500 ÷ 3000
SI	59	90	116
TR	120	-	-

NOTE TECNICHE - TECHNICAL NOTES

- Realizzazione di controtelai con intervalli in altezza e larghezza ogni 50 mm. • Per sede interna (SI) da 59 mm è consigliabile pannello porta con SP max 44 mm, comprese eventuali cornici fermavetro. • Dimensioni disponibili a richiesta: L=500 ÷ 1500 mm e H=500 ÷ 3000 mm.
- La dotazione standard comprende nr.2 scatole elettriche a 3 moduli (spessore 40 mm) e nr. 2 tubi corrugati premontati Ø 20 mm. È inoltre cablato nr.1 cavo di terra su ogni lato del controtelaio. È possibile inserire fino a nr.3 tubi idraulici per lato con Ø max 25 mm compreso isolamento. Le predisposizioni per la posa di nr. 3 tubi corrugati Ø 16/20/25 mm per le utenze elettriche sono presenti su entrambi i lati del controtelaio.
- Per misure speciali verificare fattibilità in azienda. • Portata standard dei carrelli 150 Kg.
- Creation of pocket frames with height and width intervals every 50 mm. • For pocket frames with internal opening (SI) 59 mm, it is advisable to install a door panel with a max. thickness of 44 mm, including any frames for glass. • Dimensions available on request: L=500 ÷ 1500 mm e H=500 ÷ 3000 mm.
- The system is supplied with n.2 socket boxes provided with 3 units (40 mm thick) and with n.2 premounted corrugated pipes Ø 20 mm. On each side of the frame there is n.1 earthing wire. It is possible to host on each side of the frame up to nr.3 plumbings with Ø max of 25 mm insulation included. The settings for the electrical wiring and sockets of n.3 corrugated pipes Ø 16/20/25 mm are on both sides of the frame. • For special dimensions, please check the feasibility with the company.
- Standard payload of the supplied hanging kit: 150 Kg.